







E1 WALL TYPE E1
1 1/2" = 1'-0"




E71 WALL TYPE E71
1 1/2" = 1'-0"




E3 WALL TYPE E3
1 1/2" = 1'-0"




A3 WALL TYPE A3
1 1/2" = 1'-0"




E42 WALL TYPE E42
1 1/2" = 1'-0"



A4 WALL TYPE A4
1 1/2" = 1'-0"




E58 WALL TYPE E58
1 1/2" = 1'-0"



A6 WALL TYPE A6
1 1/2" = 1'-0"

WALL TYPE GENERAL NOTES

- REFER TO STRUCTURAL FOR ADDITIONAL INFORMATION INCLUDING GROUTING AND REINFORCING.
- REFER TO SPECIFICATION MANUAL FOR ADDITIONAL INFORMATION.
- PROVIDE WATER RESISTANT GYPSUM BOARD AT ALL WET LOCATIONS.
- PROVIDE TILE BACKER BOARD IN LIEU OF GYPSUM BOARD AT ALL WALL TILE LOCATIONS.
- REFER TO FINISH PLANS & ELEVATIONS FOR FINISH INFORMATION.
- ALL PARTITIONS EXTEND TO DECK UNLESS OTHERWISE NOTED.
- REFER TO RCP FOR WALL HEIGHTS AND TOP OF WALL DETAILS - SEE SHEETS A201.
- NON-STRUCTURAL LIGHT GAUGE METAL FRAMING SHALL BE MINIMUM 22 GAUGE U.N.O.
- NO FIRE RATED SEPARATIONS IN PROJECT



A10 WALL TYPE A10
1 1/2" = 1'-0"

INTERIOR FRAMING LIMITING HEIGHTS

STUD DEPTH MM(IN.)	STUD SPACING MM IN.	DESIGN PA PSF	ALLOWABLE DEFLECTION	25 GAUGE (18 MIL) 0.455 MM MIN. (0.01799" MIN.)		20 GAUGE (33 MIL) 0.836 MM MIN. (0.03299" MIN.)	
				MM	(FT-IN.)	MM	(FT-IN.)
41mm (1-5/8")	(162S125-18/33)	600 24	240 5	L/120	2970 (9'-9")	3350 (11'-0")	
41mm (1-5/8")	(162S125-18/33)	600 24	240 5	L/240	2410 (7'-11")	2670 (8'-9")	
41mm (1-5/8")	(162S125-18/33)	600 24	240 5	L/360	2160 (7'-1")	2340 (7'-8")	
41mm (1-5/8")	(162S125-18/33)	400 16	240 5	L/120	3230 (10'-7")	3680 (12'-1")	
41mm (1-5/8")	(162S125-18/33)	400 16	240 5	L/240	2540 (8'-4")	2950 (9'-8")	
41mm (1-5/8")	(162S125-18/33)	400 16	240 5	L/360	2490 (8'-2")	2370 (8'-5")	
64mm (2-1/2")	(250S125-18/33)	600 24	240 5	L/120	3610 (11'-10")	4520 (14'-10")	
64mm (2-1/2")	(250S125-18/33)	600 24	240 5	L/240	3230 (10'-7")	3530 (11'-7")	
64mm (2-1/2")	(250S125-18/33)	600 24	240 5	L/360	2820 (9'-3")	3050 (10'-0")	
64mm (2-1/2")	(250S125-18/33)	400 16	240 5	L/120	4040 (13'-3")	5000 (16'-5")	
64mm (2-1/2")	(250S125-18/33)	400 16	240 5	L/240	3430 (11'-3")	3910 (12'-10")	
64mm (2-1/2")	(250S125-18/33)	400 16	240 5	L/360	3000 (9'-10")	3400 (11'-2")	
92mm (3-5/8")	(362S125-18/33)	600 24	240 5	L/120	4190 (13'-9")	5640 (18'-6")	
92mm (3-5/8")	(362S125-18/33)	600 24	240 5	L/240	4090 (13'-5")	4500 (14'-9")	
92mm (3-5/8")	(362S125-18/33)	600 24	240 5	L/360	3530 (11'-7")	3890 (12'-9")	
92mm (3-5/8")	(362S125-18/33)	400 16	240 5	L/120	4670 (15'-4")	6300 (20'-8")	
92mm (3-5/8")	(362S125-18/33)	400 16	240 5	L/240	4370 (14'-4")	5000 (16'-5")	
92mm (3-5/8")	(362S125-18/33)	400 16	240 5	L/360	3760 (12'-4")	4340 (14'-3")	
102mm (4")	(400S125-18/33)	600 24	240 5	L/120	4600 (15'-1")	6320 (20'-9")	
102mm (4")	(400S125-18/33)	600 24	240 5	L/240	4520 (14'-2")	5000 (16'-5")	
102mm (4")	(400S125-18/33)	600 24	240 5	L/360	3760 (12'-4")	4340 (14'-3")	
102mm (4")	(400S125-18/33)	400 16	240 5	L/120	5230 (17'-2")	7040 (23'-1")	
102mm (4")	(400S125-18/33)	400 16	240 5	L/240	4670 (15'-4")	5590 (18'-4")	
102mm (4")	(400S125-18/33)	400 16	240 5	L/360	4060 (13'-4")	4850 (15'-11")	
152mm (6")	(600S125-18/33)	600 24	240 5	L/120	5110 (16'-9")	8280 (27'-2")	
152mm (6")	(600S125-18/33)	600 24	240 5	L/240	5110 (16'-9")	6580 (21'-7")	
152mm (6")	(600S125-18/33)	600 24	240 5	L/360	5110 (16'-9")	5740 (18'-10")	
152mm (6")	(600S125-18/33)	400 16	240 5	L/120	6020 (19'-9")	9400 (30'-10")	
152mm (6")	(600S125-18/33)	400 16	240 5	L/240	6020 (19'-9")	7470 (24'-6")	
152mm (6")	(600S125-18/33)	400 16	240 5	L/360	5460 (17'-11")	6500 (21'-4")	

NOTES: THEN NUMBER FOLLOWING THE STUD DEPTH IS A NEW INDUSTRY-WIDE PRODUCT IDENTIFICATION, CREATED BY THE STEEL STUD MANUFACTURERS ASSOCIATION; (U.S.) THE NUMBER IDENTIFIES THE MEMBER DEPTH, STYLE, FLANGE WIDTH AND MATERIAL THICKNESS IN MILS.

THIS LIMITING HEIGHTS DATA IS FROM ASTM C754. CGC PRESENTS THIS INFORMATION ONLY AS A REFERENCE, AND WILL NOT BE RESPONSIBLE FOR THE PERFORMANCE OF WALLS BASED ON THIS TABLE. CONSULT CURRENT INFORMATION FROM ASTM C754 AND SSMA (STEEL STUD MANUFACTURERS ASSOCIATION), AND THE STUD MANUFACTURERS FOR LIMITING HEIGHTS CHARACTERISTICS OF THEIR PARTICULAR PRODUCTS.

LIMITING HEIGHTS APPLY TO WALLS CONSTRUCTED WITH MINIMUM 12.7 MM (1/2") THICKNESS OF GYPSUM BOARD AND WITH A MINIMUM OF ONE FULL-HEIGHT LAYER ON BOTH SIDES OF THE STUD FRAMING.


LIMITING HEIGHTS ARE BASED ON TESTS CONDUCTED WITH GYPSUM BOARD ATTACHED WITH SCREWS SPACED 300MM (12") O.C. TO FRAMING MEMBERS.

STEAM CLASSROOM BUILDING
NORTHLAND PREPARATORY ACADEMY
3300 SPARROW AVE
FLAGSTAFF, AZ 86004
WALL TYPES

THIS DRAWING IS AN INSTRUMENT OF SERVICE & IS THE PROPERTY OF SPS-ARCHITECTS LLP & MAY NOT BE REPRODUCED OR REPRODUCTIONS HEREOF USED WITHOUT WRITTEN PERMISSION.

REVISIONS		
MARK	DATE	DESCRIPTION
1	5/16/24	CITY COMMENTS

REVIEWED BY: AT
DRAWN BY: ALP



CONSTRUCTION SET
ASI 01 06-21-2024

JOB No: K2300049

SHEET:

A102